

Matrix of New Spaces with Finishes - Room Size per POR

Space	RPS layout number(s) to be used if applicable	Floor	Wall	Ceiling	Furniture	Comments
Exercise Room	—	Resilient athletic flooring - Spec 09626	Gyp Bd	Act		Wall padding for PS
D75 Sensory gym	—	Resilient athletic flooring Spec 09626	Gyp Bd wall and column padding	Act	Project specific Loose play equipment	Project specific Indirect lighting only
Dance Studio	4-11 w/o storage room	wood	Gyp Bd	Act	Provide storage closet or open storage shelving if requested by school	
Gymnasium w/moveable bleachers	4-70, 4-90 for gym and stage components only	wood	Block/acoustic block, add'l acoustic treatment if recommended	Project specific	Stage along long side of gym fronting ½ of gym for gym w/ folding partition. Bleacher seating along long side of gym for ½ of gym for gym w/ folding partition	Allocate additional 250 SF alcove for bleachers
Rooftop Greenhouse		Concrete spec 09675 or Ceramic tile	Kneewall with quarry or ceramic tile finish	--	Work tables for planting, floor drain, sink, shelving for storage, wall mounted hose bibb, flexible hose, hose reel. Mechanical requirements and glazing type (IGU vs single glazed) will vary depending on location and attachment to building. E.g. attached to corridor and sharing walls with other spaces vs detached or standalone	Fixed/operable glazing @ walls, skylights
Hydroponic Classroom		Concrete Spec 09675	Kneewall with quarry or ceramic tile finish	--	Work tables for planting, floor drain, sink, shelving for storage, wall mounted hose bibb, flexible hose	Fixed/operable glazing @ walls, skylights
Robotics Lab	Project specific				Project specific	Project specific
Library	6-10,11,12	VCT	Gyp Bd	Act	stations Provide sink that was in office in an area near the Librarian's desk Circulation desk/counter, book drop, no dictionary stand	w/o librarians office w/o library workroom
Guidance/SBST suite	8-10.1, 8-10.2 and 8-30.1	VCT	Gyp Bd	Act		
D75 Main office	CW40-70				Include photocopier in office. Include shelving units in office if separate D75 storage is not in vicinity of D75 office.	
D75 OT Room	CW34-00				Provide a minimum of one of each component.	
D75 PT Room	CW34-00				Provide a minimum of one of each component.	
D75 Multi-purpose Room	Project specific			Act	Project specific	Project specific
D75 Resource Room	1-32	VCT	Gyp Bd	Act	Provide a minimum of one of each component.	
Vault	9-22	Concrete or VCT	CMU	None or Gyp Bd	Provide shelving	Avoid using a "safe". Space can be as small as a 50 SF closet with CMU walls and HM door.